

PROMETAL S.R.
Milosava Vlajića 49
11450 Sopot
Serbia
EUROPE
Tel. +381.63.133.44.56
+381.63.8623.758
Fax +381.11.283.41.39
web site: www.eg-prometal.rs
bank: Raiffeisen Bank – Serbia

Date: August 9, 2011.

Offer No: 52/2011.

Dear gentlemen,

We appreciate your interest in our machines and are pleased to submit you the following quotation according to the "General Terms of Delivery of the PROMETAL – Construction machines productions, Sopot, Belgrade, Serbia".

**MOVABLE CONCRETE BLOCK MAKING MACHINE
EGG LAYER TYPE**

EUROBLOCK 6

SEMI – AUTOMATIC MODEL

OFFER : Concrete block making machine EB-6 SA

Dear gentlemen,

We appreciate your interest in our machines and are pleased to submit you the following quotation according to the "General Terms of Delivery of the PROMETAL – Construction machines productions, Sopot, Belgrade, Serbia".

Description:

Concrete block making machine EB – 6 is egglayer type machine, (that strips blocks on floor) used for manufacturing:

- **Hollow blocks**
- **Solid blocks**
- **Chimney blocks**
- **Hourdy blocks**
- **Curbstones**

All machine movements are hydraulically operated, with hydraulic distributors. Feeding of mould with concrete is by hydraulically driven filling box. Steering of machine is done by 3th wheel with gear reducer working on it. High speed vibrators ensure high quality products, and optimum production cycle time. All electrical and mechanical parts are manufactured by world known manufacturers (Siemens, ABB, Vickers, Marzocchi, Salami...).
Maintenance and service works are minimal due to strong built frame and excellent quality of components.

Technical data:

Operation mode	semiautomatic
Max block height	350 mm
Min block height	170 mm
Mould production area max	1250x500 mm
Concrete hopper volume	500 l
Machine weight	2.000 kg
Consumption of electricity	10kW
Voltage supply	3x400V, 50 Hz (different values on request)
Control voltage	24V DC + 230 V AC
Production capacity	500-700 blocks/hour (20x20x40 cm hollow block)









Needed side equipment:

To work with full production capacity with machine EB – 6 optimal is to have next side equipment

- **Concrete mixer type DZB 800 with mobile loading skip (or mini batching plant MCM 400)**
- **Damper for transport concrete from mixer to machine (or movable hopper to attach on forklift)**
- **Clamps for collecting blocks from floor (attachment for usual forklift)**



Scheme of the plant

Technical data for mixer DZB 800 with skip:

Mixer loading volume 500 l
Output per batch vibrated concrete 330 l
Max load capacity in kg 800 kg
Mixer motor power 11 kW

Skip volumetric capacity 500 l
Skip motor power 3 kW



DELIVERY TERMS

The delivery of offered machine EUROBLOCK 6 will be separated in several phases [periods]:

1. Production of all machines offered by Prometal.....60 days.
2. Transport to client's location depends from Transport Company and location of buyer.
3. Set up and giving the training to client's stuff..... 4 - 6 days.

Way of payment

Bank transfer on manufacturers account will be paid in EUR € [EMU] European money unit, 30% FOR CONFIRMATION ORDER. Client will get our bank guarantees for 30% paid advance. Through line of credit [L/C] for rest 70% payable at sight and confirmed by Serbian bank. Confirmation costs outside of SERBIA are on customers charge.

Maintenance

Buyer will get all needed MANUALS for working with the machine, detailed, on English language. This MANUAL will include details about maintaining the machines, too. The manual for SPARE parts is included, too.

Spare parts

All spare parts for the machines are available from the manufacturer, factory or can be bought on the market.

GUARANTEE PERIOD

GUARANTEE PERIOD is 12 months from the date of machine putting in operation according to standard guarantee conditions.

The Guarantee DOES NOT include:

- The consignments will be charge collect.
- Does not include the maintenance works of the machinery neither the consumable.
- Does not include no piece evertasting: oils, grease, filters.
- The electrical material defects-electronic due to rises-descents of entry tension.
- Maintenance and hotel expenses, return flight tickets.

THE FOLLOWING CONCEPTS ARE CHARGE TO THE CLIENT:

- The BUILDING & civil engineering.
- DOES NOT include anything that is NOT quoted in the offer.
- Hydraulic Oil
- The client will provide 2 persons, 8 hours per day for the help, without charge for Prometal.

WORKS TO BE MADE BY THE CLIENT:

- Discharge of the machinery until the factory, through a crane and forklifts.
- Transportation of the personal of Prometal from the Hotel to Factory and conversely.
- Connection to the electrical power network.

The technical descriptions of the machines are held to the possible changes that they could be effected to date of delivery of the machinery. The technical descriptions of the offers have priority before any catalogues description.